



COMPACTION NOTES:

(GENERAL)

- ALL AREAS TO BE FILLED SHALL BE COMPLETELY CLEARED OF ALL DELETERIOUS MATERIAL, INCLUDING THE FOLLOWING: TREES, ROOTS AND ALL OTHER DECAYED VEGETATION.
- PRIOR TO THE COMMENCEMENT OF ANY CIVIL OR STRUCTURAL CONSTRUCTION THE ENTIRE SITE AREA IS TO BE COMPACTED AND TESTED IN ACCORDANCE WITH AS1289.5.1.1 OR .5.1.2 - 1993 TO PRODUCE THE FOLLOWING:
-98.0% STANDARD COMPACTION AT THE SURFACE AND AT 200mm BELOW SURFACE LEVEL. FREQUENCY OF FIELD DENSITY TESTS SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3798 - 2007 TABLE 8.1. TESTING SHALL BE EVENLY SPACED OVER THE ENTIRE SITE, AND AT RANDOM LOCATIONS. TEST RESULTS SHALL BE FORWARDED TO THE ENGINEER FOR APPROVAL PRIOR TO COMMENCEMENT OF WORKS.
- ALL NEW FILL MATERIAL SHALL BE APPROVED BY THE ENGINEER AND SHALL BE COMPACTED TO PRODUCE 98% STANDARD COMPACTION IN ACCORDANCE WITH AS1289.5.1.1.
THE LOOSE THICKNESS OF EACH LAYER BEFORE COMPACTION SHOULD NOT EXCEED 200mm WITHOUT THE APPROVAL OF THE ENGINEER. PROVIDE COMPACTION TESTS FOR NEW FILL AS PER NOTE 2.
- ALL EXISTING FILL WITHIN THE CONSTRUCTION AREA SHALL BE COMPLETELY REMOVED. MATERIAL SHALL BE REPLACED AND COMPACTED IN LAYERS NOT EXCEEDING 200mm WHEN MEASURED LOOSE. EACH LAYER SHALL BE COMPACTED TO ACHIEVE A DENSITY OF NOT LESS THAN 98.0% (FOR COMMERCIAL) AND 95% (FOR RESIDENTIAL) STANDARD COMPACTION, AND TESTED AS PER NOTE 2.

COMPACTION NOTES:

(PAVEMENTS)

- BASE MATERIAL NORMALLY CONSTRUCTED OF 20.0mm F.C.R. SHALL BE COMPACTED TO ACHIEVE A DENSITY NOT LESS THAN 98.0% OF THE MODIFIED COMPACTION IN ACCORDANCE WITH AS1289.5.2.1 - 1993. FREQUENCY OF FIELD DENSITY TESTS SHALL BE CARRIED OUT IN ACCORDANCE WITH AS3798 - 2007 TABLE 8.1. TESTING SHALL BE EVENLY SPACED OVER THE ENTIRE SITE, AND AT RANDOM LOCATIONS. TEST RESULTS SHALL BE FORWARDED TO THE ENGINEER FOR APPROVAL PRIOR TO COMMENCEMENT OF WORKS.
- SUB-BASE MATERIAL NORMALLY CONSTRUCTED OF 20.0mm TO 40.0mm Q.R. SHALL BE COMPACTED TO ACHIEVE A DENSITY NOT LESS THAN 95.0% OF THE MODIFIED COMPACTION IN ACCORDANCE WITH AS1289.5.2.1 - 1993 -TESTING SHALL BE CARRIED OUT AS NOTE 1.

CONCRETE NOTES:

- CONCRETE SHALL COMPLY, AS REGARDS TO BOTH MATERIALS AND WORKMANSHIP, WITH AS3600 "CONCRETE STRUCTURES CODE".
- KERB AND GUTTER TO COMPLY WITH AS2876-1987.
- CONCRETE SHALL BE OBTAINED FROM AN APPROVED PRE-MIX SUPPLIER AND SHALL COMPLY WITH THE CURRENT AS1379 "SPECIFICATION FOR READY MIXED CONCRETE". THE CONCRETE SHALL HAVE A SLUMP OF 80mm AND A COMPRESSIVE STRENGTH OF $f'c=25MPa$ FOR KERBS AND PITS (U.N.O.) AT TWENTYEIGHT (28) DAYS. AGGREGATE SIZE SHALL BE 20mm.
- STEELWORK FOR REINFORCEMENT AND JOINT CONSTRUCTION SHALL COMPLY, AS REGARDS TO BOTH MATERIALS AND WORKMANSHIP, WITH AS3600 "CONCRETE STRUCTURES CODE".
- SHRINKAGE- CONTROL JOINTS ON KERB, KERB AND GUTTER, EDGING AND SPOON DRAIN SHALL BE FORMED AT SPACINGS OF 2500c/c WITH A TOOLED GROOVE TO A DEPTH OF NOT LESS THAN 20mm AND PROVIDE WEAKENED PLANE TO FULL DEPTH.

GENERAL NOTES:

- THIS IS AN ENGINEERING SURVEY PLAN AND SHALL NOT BE TAKEN AS A CADASTRAL OR IDENTIFICATION SURVEY. BOUNDARY DATA SHOWN IS TO BE TAKEN AS A GUIDE ONLY.
- BEFORE SETTING OUT PIPE RUNS, REFER TO THE ARCHITECTURAL, MECHANICAL, STRUCTURAL AND ALL OTHER RELEVANT DRAWINGS TO PREVENT CLASHING OF SERVICES.
- REFER TO DIMENSIONED ARCHITECTURAL BUILDING DETAILS FOR ALL SETTING OUT DIMENSIONS AND CO-ORDINATE WITH SITE PROJECT MANAGER.
- TMK CONSULTING ENGINEERS ACCEPT NO RESPONSIBILITY FOR ERRORS AND OMISSIONS RELATED TO DIMENSIONAL SET-OUT OR DISCREPANCIES MADE BY THIRD PARTIES DURING CONSTRUCTION.
- REFER TO STRUCTURAL ENGINEER'S DRAWINGS FOR DETAILS OF CONCRETE FLOOR AND BEAMS BEFORE SETTING OUT.
- PROVIDE MINIMUM COVER TO STORMWATER PIPES AS PER AS3500 U.N.O. IF COVER CAN NOT BE ACHIEVED ENCASE PIPE IN 100mm THICK CONCRETE. ALL STORMWATER AND/OR OTHER SERVICE CONNECTION POINTS ARE TO BE LOCATED AND CONFIRMED BY THE BUILDER/CONTRACTOR PRIOR TO THE COMMENCEMENT OF ANY CIVIL WORKS.
- FLEXIBLE CONNECTIONS FOR SEWER AND STORMWATER ARE REQUIRED FOR THIS SITE.
- ALL NEW CIVIL WORKS ARE TO BE CONSTRUCTED TO MATCH IN NEATLY WITH EXISTING STRUCTURES.
- CONTRACTOR TO CONFIRM EXISTING FINISHED FLOOR LEVEL ON SITE. FINISHED FLOOR LEVEL OF ADDITION TO MATCH EXISTING.

LEGEND

- S.J. — SOFF CUT JOINT (REFER DETAIL)
D.J. — DOWELLED JOINT (REFER DETAIL)
C.J. — EXPANSION JOINT (REFER DETAIL)

C	REVISED APPROVAL ISSUE	JB	ASM	20.12.19
B	FOR BUILDING APPROVAL	ALP	FKK	26.06.19
A	FOR BUILDING APPROVAL	ALP	FKK	17.05.19
No	REVISION		DRAWN/CHE/KD	DATE

PROJECT
PROPOSED APARTMENT
AT: 90 JOHNS ROAD
PROSPECT
FOR: CITIFY & BFC Pty Ltd

DRAWING TITLE
JOINT LAYOUT PLAN, NOTES & DETAILS

Civil Environmental Mechanical Fire Lifts	Structural Geotechnical Electrical Hydraulics Green ESD
Level 6, 100 Pirie Street, Adelaide SA 5000 Telephone 08 8238 4100 Facsimile 08 8410 1405 Berri Office: 25 Vaughan Terrace, Berri SA 5343	

SCALES AS SHOWN	© COPYRIGHT RESERVED
DRAWN ALP	DRAWING No.
DATE AUG '18	1806063-C2/C
ENGINEER ALP	
CHECKED FKK	