



NOTE:  
VENTS SHALL TERMINATE AT MINIMUM 150mm ABOVE ROOF  
IN ACCORDANCE WITH AS/NZS3500. PROVIDE WIND DRIVEN  
VENT COWLS TO ALL TRADE WASTE VENTS IN ACCORDANCE  
WITH 'SA WATER CORPORATION' TRADE WASTE GUIDELINES.

NOTE:  
ALL SEWER AND TRADE WASTE PIPEWORK SHALL BE  
INSTALLED AT THE FOLLOWING MINIMUM GRADES  
UNLESS OTHERWISE STATED:  
• Ø40-Ø65 : 2.50% MINIMUM  
• Ø100 : 1.65% MINIMUM  
• Ø150 : 1.00% MINIMUM  
ALL VENT PIPEWORK SHALL BE INSTALLED AT 125%  
MINIMUM GRADE UNLESS OTHERWISE STATED.

3 OFF MANUFACTURER APPROVED COAXIAL  
FLUES EXTENDING FROM INTERNAL GAS FIRED  
HOT WATER UNIT BELOW TERMINATING ABOVE  
ROOF IN ACCORDANCE WITH ASS601.

PROVIDE 150x150x150 TRAPPED TUNDISH  
SET 50mm ABOVE ROOF FOR RECEIPT OF  
MECHANICAL SERVICES CONDENSATE  
AND EXTEND Ø50 TRAPPED WASTE TO  
ADJACENT SEALED GULLY TRAP.

CONSTRUCTION ISSUE

REV	DESCRIPTION	DATE	CHK'D
A	CONSTRUCTION ISSUE	21.09.18	AS

LUCID  
CONSULTING AUSTRALIA  
Level 3/169 Pirie St Adelaide SA 5000  
Phone: (08) 8407 9700  
Email: adelaide@lucidconsulting.com.au

CITIFY

bfc

PROJECT  
THE WILLCOX APARTMENTS  
117 PROSPECT ROAD, PROSPECT

DRAWING  
ROOF  
SANITARY DRAINAGE ARRANGEMENT

HYDRAULIC SERVICES

SCALE 1:100@A1	DATE SEPTEMBER 2018
DESIGNED JZ	DRAWN JZ/ML
No. IN SET 8 OF 17	
DRAWING NUMBER LCE13523-H08	
REVISION A	